

# VEU MRL HOME ELEVATOR 36" (900mm) 2 SPEED AUTOMATIC (FRONT)

MAX GROSS LOAD	2000 Lbs (910 Kg)
CAPACITY	950 Lbs (430 Kg)
MAX TRAVEL	42 ft (12.9 m)
MAX LANDINGS	5 FLOORS
MAX FLOOR AREA	15 sq/ft (1.4 sq/m)

CAR WIDTH (A)	CAR DEPTH (B)	HOISTWAY WIDTH (C)	HOISTWAY DEPTH (D)	RETURN (E)	STRIKE (F)	INSIDE CAR AREA
36	46	60	59	19.50	5.13	11.50 (1.07)
	48		61			12.00 (1.12)
	50		63			12.50 (1.16)
	52		65			13.00 (1.21)
	54		67			13.50 (1.25)
	56		69			14.00 (1.30)
	58		71			14.50 (1.35)
38	46	62	59	21.50		12.14 (1.13)
	48		61			12.67 (1.18)
	50		63			13.19 (1.23)
	52		65			13.72 (1.28)
	54		67			14.25 (1.32)
	56		69			14.78 (1.37)
40	46	64	59	23.50		12.78 (1.19)
	48		61		13.33 (1.24)	
	50		63		13.89 (1.29)	
	52		65		14.44 (1.34)	
	54		67		15.00 (1.39)	
42	46	61	59	20.75	5.38	13.42 (1.25)
	48		61			14.00 (1.30)
	50		63			14.58 (1.36)

